BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFIED SCHEDULE - B

Name of the Work : Supply and Instalation of CCTV Camaras at Selected Points and Maintenance of Existing CCTV Cameras in Ward No. 09, Amruthahalli.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2.00	Outdoor PLZ IP Cameras with 20 X optical zoom with controller along with suitable mounting system (PTZ Pan Tilt and Zoom feature is availbale in this camera can be contolled by the software for pan Tilt and zoom feature at the contol center and can be programmed to view at different angles and zoom level continuosly. It operates at day and night and the viewing distance at clarity is about 100 metres	Nos	65751.16	Rupees Sixty Five Thousand Seven Hundred Fifty One And Paise Sixteen Only
2	8.00	Bracket (Corner Mount / Pole Mount/ Wall Mount) for mounting the PTZ camera.	Nos	3575.75	Rupees Three Thousand Five Hundred Seventy Five And Paise Seventy Five Only
3	8.00	Outdoor 50 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 50 metres)	Nos	17732.08	Rupees Seventeen Thousand Seven Hundred Thirty Two And Paise Eight Only
4	9.00	Bracket and weatherproof Installation kit for 50 Meter IP Camera	Nos	1294.71	Rupees One Thousand Two Hundred Ninety Four And Paise Seventy One Only
5	8.00	Outdoor 30 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 30 metres)	Nos	12787.88	Rupees Twelve Thousand Seven Hundred Eighty Seven And Paise Eighty Eight Only
6	9.00	Bracket and weatherproof Installation kit for 30 Meter IP Camera	Nos	1249.46	Rupees One Thousand Two Hundred Forty Nine And Paise Forty Six Only
7	3.00	32 Channel NVR DS 7732 NI- E4 (with 4 Sata Option) the control box and the recording device to connect upto 32 devices, can be cascaded to provide additional cameras	Nos	56130.92	Rupees Fifty Six Thousand One Hundred Thirty And Paise Ninety Two Only
8	2.00	12 TB NAS Box for Back up (NET GEAR) provides storage for the recorded data for quick view back and storage	Nos	215718.00	Rupees Two Lakh(s) Fifteen Thousand Seven Hundred Eighteen Only
9	4.00	4 TB SATA for storage and fitted in the NVR Device for storage	Nos	19148.30	Rupees Nineteen Thousand One Hundred Forty Eight And Paise Thirty Only
10	9.00	A suitable sheet metal control panel to house site Equipments (Weather Proof) The power supply and the ethernet connectivity adaptor is stored in this box.	Nos	1278.79	Rupees One Thousand Two Hundred Seventy Eight And Paise Seventy Nine Only
11	9.00	Power supply for the camera.	Nos	386.32	Rupees Three Hundred Eighty Six And Paise Thirty Two Only

Signature of the Contractor

Executive Engineer

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
12	9.00	Ethernet Switch for connectivity to Internet and Camera	Nos	796.10	Rupees Seven Hundred Ninety Six And Paise Ten Only
13	9.00	Supply & Laying of Network and Power Cables from Camera to the control Box.	Nos	325.99	Rupees Three Hundred Twenty Five And Paise Ninety Nine Only
14	9.00	Video Manager Application Software for Display and Management of Camera on Video Display.	Nos	16760.00	Rupees Sixteen Thousand Seven Hundred Sixty Only
15	9.00	Installation, Erection & commissioning charges	Nos	4240.30	Rupees Four Thousand Two Hundred Forty And Paise Thirty Only
		EIRL			
E1	5.00	Providing CCTV MS Poles with camera fixing brackets 5 to 6Mtrs hight box inclusive of all taxes transortation charges as per the direction of engineer incharge.	Nos	19693.00 18447.50	(2) Rupees Eighteen Thousand Four Hundred Forty Seven And Paise Fifty Only

Ninteen thousand six hundred ninty three only.

Signature of the Contractor

No. of Corrections = 2 (Two)

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃಬೆಂ.ಮ.ಪಾ. ಬೆಂಗಳೂರು.

ಕಾ.ಅ. (ಬ್ಯಾವಿ.)
ಬೃಬೆಂ.ಮ.ಪಾ.